

(工事費内訳書)

本工事費

費目・工種・種別・細別・施工名称など		数	量	単	位	単	価	金	額	備	考
水路工事											
			1		式						
	掘削									[R7黄本P1015 / R7赤本PⅡ-1-②-7]	
	土砂 小規模 小規模(標準)		20		m3						
	基面整正									[R7黄本P1052 / R7赤本PⅡ-1-③-7]	
			13		m2						
	埋戻し									[R7黄本P1056 / R7赤本PⅡ-1-③-12]	
	小規模 土砂		4		m3						
	積込(ルース)									[R7黄本P1035 / R7赤本PⅡ-1-②-27]	
	土砂 小規模(標準)		16		m3						
	土砂等運搬									[R7黄本P1021 / R7赤本PⅡ-1-②-13]	
	小規模 4.0km以下		16		m3						
	残土等処分									[R7黄本P1038 / R7赤本PⅡ-1-②-30]	
			16		m3						
	自由勾配側溝(標準単価)									[R7赤本PVI-1-⑥-1]	
	横断VS500*700		13		m						
	蓋版(標準単価)									[R7赤本PVI-1-⑥-2]	
	横断用500型[T-25]ホルト付		6		枚						

(工事費内訳書)

本工事費

費目・工種・種別・細別・施工名称など		数	量	単	位	単	価	金	額	備	考
	凍上抑制工									[R7黄本P1427 / R7赤本PIV-1-①-5]	
	200mm 1層施工 再生クラッシュランRC-40		11		m2						
	下層路盤									[R7黄本P1427 / R7赤本PIV-1-①-5]	
	190mm 1層施工 再生クラッシュランRC-40		11		m2						
	上層路盤									[R7黄本P1433 / R7赤本PIV-1-①-11]	
	100mm 1層施工 粒度調整碎石M-40		11		m2						
	不陸整正									[R7黄本P1424 / R7赤本PIV-1-①-2]	
	補足材料無		11		m2						
	表層									[R7黄本P1448 / R7赤本PIV-1-②-8]	
	1.4m未満50mm 再生密粒度アスコン(20F)		1		m2						
	掘削									[R7黄本P1015 / R7赤本PⅡ-1-②-7]	
	土砂 小規模 小規模(標準)		93		m3						
	土砂等運搬									[R7黄本P1021 / R7赤本PⅡ-1-②-13]	
	小規模 4.0km以下		93		m3						
	残土等処分									[R7黄本P1038 / R7赤本PⅡ-1-②-30]	
			93		m3						
	除根									[R7黄本P1015 / R7赤本PⅡ-1-②-7]	
			5		m3						

(工事費内訳書)

本工事費

費目・工種・種別・細別・施工名称など	数	量	単	位	単	価	金	額	備	考2
根株運搬									[R7黄本P1021 / R7赤本PⅡ-1-②-13]	
小規模 4.0km以下		5		m3						
根株処分									[R7黄本P1038 / R7赤本PⅡ-1-②-30]	
		5		t						
＊＊直接工事費＊＊										
		1		式						
＊＊共通仮設費率計算額＊＊										
		1		式						
＊＊共通仮設費計＊＊										
		1		式						
＊＊純工事費＊＊										
		1		式						
＊＊現場管理費＊＊										
		1		式						
＊＊工事原価＊＊										
		1		式						
＊一般管理費等＊										
		1		式						

（工事費内訳書）

＊ ＊ ＊ 本 工 事 費 ＊ ＊ ＊

費目・工種・種別・細別・施工名称など	数	量	単	位	単	価	金	額	備	考
＊＊工事価格計＊＊										
		1		式						
＊＊消費税等相当額計＊＊										
		1		式						
＊＊工事費計＊＊										
		1		式						